

INSPECTION AND TEST PLAN — PLASTERING AND DRYLINING

Framing, services and infill before the wall closes, fire-stopping before ceilings, finish level under the viewing conditions

PLAN — ONE PER PACKAGE

KD-ITP-DL-028 Rev A0

An inspection and test plan is the list of what will be inspected or tested at each stage of this package, against what acceptance criterion and how often, who holds the work, witnesses it, keeps it under surveillance or reviews the record, and which record proves it. On a drylining package the wall is checked three times before it closes — framing, services and infill — and the fire-stopping at heads and services is released before the ceiling; the finish level is judged under the viewing conditions the specification names, not under a torch. The stages below are the ones the area checklists cover, so the R column points to a sheet that exists — the KD-QA sheets are the records; the package cover sheet KD-QA-SYS-001 is the cover the client signs with the register of sheets raised under it; this is the plan behind both. Where this plan exists, section 3 of KD-QA-SYS-001 (and of KD-QA-PD-100 for decoration) is completed as "see this plan" and the letters are agreed here, so nothing is agreed twice. Nothing on this sheet is an acceptance value: the specification reference and the criterion are written in from the specification, and H, W, S and R are agreed with the client before the first stage starts. A failed hold raises KD-QA-SYS-007 and the line stays open until it is re-inspected.

1 PACKAGE

PROJECT / SITE REF	SITE	DATE	PACKAGE / SUBCONTRACTOR	PLAN PREPARED BY
SPECIFICATION, DRAWINGS AND REVISIONS THIS PACKAGE IS BUILT TO	PRINCIPAL CONTRACTOR'S REVIEWER	CLIENT'S REPRESENTATIVE	NOTICE FOR H AND W POINTS	PLAN REV

2 THE PLAN — ONE LINE PER STAGE, IN THE ORDER THE WORK IS BUILT

H hold — work stops until released · W witness — notice given, work proceeds if they do not attend · S surveillance — checked without stopping the work · R review of the record only. One letter per party per line; a blank means that party takes no part in the stage.

NO	STAGE / ACTIVITY	SPEC REF	INSPECTION OR TEST	ACCEPTANCE	FREQUENCY	SUB	PC	CLIENT	RECORD REF	SIGN-OFF
1	Set-out		Against the drawing		Each area				KD-QA-DL-001	
2	Head and base tracks and the deflection head		Fixings and the deflection allowance		Each wall				KD-QA-DL-001	
3	Studs, openings and fixings		Centres and openings - before boarding		Each wall				KD-QA-DL-001	
4	Services in the wall - the M&E sign-off		Complete before closing		Each wall				KD-QA-DL-002	
5	Pattresses and fixing plates		Every position on the drawing		Each wall				KD-QA-DL-002	
6	Insulation and acoustic infill		Fitted before the wall is closed		Each wall				KD-QA-DL-003	
7	First layer boarding - fire and acoustic walls		Board type, fixings, joints		Each wall				KD-QA-DL-004	
8	Second and subsequent layers		Staggered joints; fixings		Each wall				KD-QA-DL-004	
9	Fire-stopping at heads and services		Tested details; labelled		Each wall				KD-QA-DL-005	
10	Release before ceilings and closing		Reviewer release		Each area				KD-QA-DL-005	
11	Taping and jointing		Level as specified		Each area				KD-QA-DL-006	
12	Finish level and flatness		Straightedge; viewing conditions		Each area				KD-QA-DL-006	
13	Skim and float - background and coats		Background accepted; coats; flatness		Each area				KD-QA-DL-007	
14	Dry lining on dabs		Dab pattern and perimeter seal before boards		Each wall				KD-QA-DL-008	

INSPECTION AND TEST PLAN — PLASTERING AND DRYLINING

continued

PLAN — ONE PER PACKAGE

KD-ITP-DL-028 Rev A0

NO	STAGE / ACTIVITY	SPEC REF	INSPECTION OR TEST	ACCEPTANCE	FREQUENCY	SUB	PC	CLIENT	RECORD REF	SIGN-OFF
15	Handover to decoration		Snags closed; moisture		Each area				KD-QA-DL-006/007	

3 SIGN-OFF CHAIN

The subcontractor prepares the plan from the specification and the sequence it will build to. The principal contractor's reviewer accepts it: the stages are complete, every record named exists, and every hold falls before the work it protects is covered. The client's representative agrees the H, W, S and R columns and the notice period. A line is closed in the last column by the party holding the highest intervention on it; the area checklists carry the signatures for the checks themselves. Revise and re-sign when the specification, the sequence or the subcontractor changes.

Prepared by — subcontractor:

PRINTED NAME	ROLE	COMPANY	SIGNATURE	DATE	TIME

Accepted by — principal contractor's reviewer:

PRINTED NAME	ROLE	COMPANY	SIGNATURE	DATE	TIME

Agreed by — client's representative:

PRINTED NAME	ROLE	COMPANY	SIGNATURE	DATE	TIME

R REVISION HISTORY

Every revision of this document, and every review that found nothing to change. The revision on the front of this sheet is the one you are holding — check kubitdocs.com for the current one before use.

Rev	Date	Class	What changed	Authorised by
D0	2026-09-02	first-issue	First issue.	— not yet approved —
A0	2026-09-02	review	Approved for issue by the author. Content unchanged from the reviewed draft; the draft status strip is removed. No independent third-party review has been carried out.	Author — director, UK principal contractor, SMSTS. Not an independent review.

Class: first-issue · material (the law, a control, a field or the scope changed — past buyers are notified) · editorial (wording or layout only) · review (checked, nothing changed) · withdrawal. Revision prefix D = draft, not approved and not for sale; A = approved for issue by the person named, on the date shown.