

Statutory basis: HSWA 1974 s.2(2)(a) and MHSWR 1999 regs 3 and 5; Work at Height Regulations 2005; Manual Handling Operations Regulations 1992; COSHH 2002 with EH40/2005 (4th edition, 2020) — wet cement is corrosive and a potent sensitiser, and resin systems sensitise on skin contact; PUWER 1998 for pumps and mixers; CDM 2015 regs 13 and 15. Where the render forms part of an external wall build-up on a relevant building, the materials are governed by Building Regulations 2010 reg 7(2) and the specification is not a matter for site — a render coat is not substituted to suit availability.

1 DOCUMENT AND PROJECT IDENTIFICATION

RAMS REFERENCE	PROJECT / SITE REF	SITE NAME AND ADDRESS	DATE PREPARED	NEXT REVIEW DATE
CLIENT / PRINCIPAL CONTRACTOR	PLANNED START	DURATION	OPERATIVES	SUPERVISING THE WORK

2 SCOPE OF WORKS

Application of resin flooring systems: substrate preparation and priming, resin coatings, screeds and self-smoothing systems, and coving and detail work.

This document does not cover: the flooring specification, substrate repair (KD-RAMS-CR-002), and application in any space that cannot be ventilated to the data sheet requirement.

SITE-SPECIFIC SCOPE, LOCATIONS AND LIMITATIONS

3 RISK ASSESSMENT — SCORE EACH RISK FOR THIS SITE, THEN ADD WHAT IS MISSING

The hazards and controls below are the starting point for this activity, written by a working main contractor. They are not complete for your site until a competent person has scored each risk, added the site-specific hazards, and struck out anything that does not apply. Rate risks High / Medium / Low before and after controls.

1. Sensitisation from resin flooring systems

At risk: Operatives

Controls: Epoxy and polyurethane resins sensitise on skin contact and, once sensitised, an operative may be unable to work with them again. Chemical-resistant gloves to the safety data sheet — not general work gloves — changed the moment they are contaminated. Contact is prevented, not washed off. Mixing and application in ventilated areas with RPE where the data sheet requires it, and the data sheet is on site before the product is opened.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

2. Respirable silica and general dust from cutting and drilling

At risk: Operatives, others in the area

Controls: On-tool extraction (M-class) or wet suppression; RPE to the COSHH assessment (FFP3, face-fit tested) where extraction cannot adequately control exposure; sheet and segregate the work area in occupied buildings.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

3. Hand-arm vibration from power tools

At risk: Operatives

Controls: Select low-vibration tools, keep cutting edges sharp, rotate operatives to keep exposure below the action value, and record trigger time where the assessment requires it.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

4. Noise from cutting, fixing and plant

At risk: Operatives, others in the area

Controls: Select quieter methods and tools where practicable; hearing protection in designated zones and for noisy operations; agree noisy-works windows with the occupier in occupied buildings.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

5. Skin contact with cements, plasters, adhesives and sealants

At risk: Operatives

Controls: COSHH assessments for every substance; gloves matched to the substance; barrier and after-work creams available; washing facilities close to the work; report skin problems early — dermatitis is a reportable trend, not a private nuisance.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

6. Interface with occupants, other trades and the public

At risk: Occupants, other trades, the public

Controls: Segregate the work area — barriers, signage, sheeting; agree access routes and working hours with the occupier; never obstruct escape routes; deliveries and waste runs outside peak movement times where agreed.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

7. Manual handling of boards, materials and components

At risk: Operatives

Controls: Mechanical aids first — trolleys, board lifters, hoists. Two-person lifts for boards and long components; order materials in manageable sizes; plan storage close to the workface; keep carrying routes clear and lit.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

8. Slips, trips and housekeeping

At risk: Everyone in the work area

Controls: Keep the workface clear, remove waste and offcuts as they are created, route leads at high level or under mats, and maintain task lighting.

INITIAL (H/M/L)	RESIDUAL (H/M/L)	SITE-SPECIFIC ADDITIONAL CONTROLS, OR N/A	ACTION OWNER	BY WHEN

Site-specific hazards not listed above — every site has at least one:

HAZARD	WHO IS AT RISK	CONTROLS	INITIAL H/...	RESIDUAL...	ACTION OWNER	BY WHEN

4 METHOD — SEQUENCE OF WORK

- 01 Confirm the system and have the safety data sheet on site before any product is opened.
- 02 Confirm ventilation is adequate to the data sheet — if it is not, the work does not start.
- 03 Prepare the substrate by grinding or shot blasting with on-tool or unit extraction; never dry grind unextracted.
- 04 Mix strictly to the data sheet in a ventilated area, in chemical-resistant gloves and eye protection.
- 05 Prime and apply in the specified sequence and thickness, working to a wet edge and away from the exit.
- 06 Barrier and sign the area with the walk-on time and the load-on time stated separately.
- 07 Dispose of part-mixed material and contaminated PPE as chemical waste, never to general site waste.

SITE-SPECIFIC AMENDMENTS TO THE SEQUENCE

5 PLANT, EQUIPMENT AND MATERIALS

- Grinders and shot blasters with extraction
- Forced-action mixers
- Spike rollers and squeegees
- Ventilation units
- Barriers and cure-time signage

INSPECTION / THOROUGH EXAMINATION REFS

COSHH ASSESSMENT REFS

6 PPE — THE LAST LINE OF CONTROL, NOT THE FIRST

- Head protection
- Safety footwear
- High visibility
- Gloves — task-rated
- Eye protection
- Hearing protection
- Chemical-resistant gloves to the safety data sheet
- RPE where the data sheet requires it
- Eye protection
- Spiked overshoes

RPE TYPE, FACE-FIT STATUS, AND ANY OTHER PPE REQUIRED

7 PERMITS REQUIRED BEFORE THIS WORK STARTS

A permit authorises this work in that place, on that day. It extends the safe system of work in this document — it does not replace it (HSE HSG250). The site issues the permit; record its number before work starts.

KD-PTW-GP-003 — General Permit to Work

For work in occupied and operating buildings.

PERMIT NUMBER

KD-PTW-CS-004 — Confined Space Entry Permit

Where resin is applied in a tank, pit or enclosed void.

PERMIT NUMBER

8 EMERGENCY ARRANGEMENTS — COMPLETE FOR THIS SITE

FIRST AIDER AND LOCATION	NEAREST A&E	ASSEMBLY POINT
HOW THE ALARM IS RAISED	EMERGENCY ACCESS FOR THIS WORK AREA	SPILL / ENVIRONMENTAL RESPONSE

9 BRIEFING RECORD — EVERYONE WORKING UNDER THIS RAMS SIGNS BEFORE STARTING

By signing you confirm the contents of this RAMS have been explained to you, you understand the hazards and controls, and you will work to the sequence stated. Tell the supervisor if the work or the site does not match this document — work stops until it does.

NAME	COMPANY	SIGNATURE	DATE

10 PREPARED AND ACCEPTED

Prepared / adapted for this site by — I confirm I have adapted this document to the site, scored the risks, and that it describes how the work will actually be done.

PRINTED NAME	ROLE / COMPETENCE	COMPANY	SIGNATURE	DATE	TIME

Accepted for the site by — principal contractor or site manager review.

PRINTED NAME	ROLE	COMPANY	SIGNATURE	DATE	TIME

Review this RAMS if the work, the site or the law changes, and at least before each new phase of the works. Flatten the completed PDF before filing so the record cannot be silently edited.

R REVISION HISTORY

Every revision of this document, and every review that found nothing to change. The revision on the front of this sheet is the one you are holding — check kubitdocs.com for the current one before use.

Rev	Date	Class	What changed	Authorised by
D0	2026-08-11	first-issue	First issue.	— not yet approved —
A0	2026-08-27	review	Approved for issue by the author. Content unchanged from D0; the draft status strip is removed. No independent third-party review has been carried out.	Author — director, UK principal contractor, SMSTS. Not an independent review.

Class: first-issue · material (the law, a control, a field or the scope changed — past buyers are notified) · editorial (wording or layout only) · review (checked, nothing changed) · withdrawal. Revision prefix D = draft; not approved and not for sale; A = approved for issue by the person named, on the date shown.